

BRUHAT BANGALORE MAHANAGARA PALIKE**DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

**Name of Work:-Improvements to Road & Drain at Nisarga layout in ward No.14
Bagalagunte**

Sl	Description of Work	Unit	Qty	Sanctioned Rates		Amount
				In figures (Rs)	In Words (Rs)	
1	2	3	4	5	6	7
1	Earthwork excavation and forming in embankment by manual means in ordinary soil with initial lead upto 15 m. and lift of 1.5m. (when earth is taken from bank cutting or from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications.	Cum	27.00	65.88	Rupees Sixty Five & Eighty eight Paise Only	1779.00
2	Removing B.S.Slab of drain and stacking etc., complete	Sqm	97.20	50.11	Rupees Fifty & Eleven Paise only	4871.00
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials,	Cum	16.20	4211.38	Rupees Four thousand two hundred eleven and thirty eight Paise only	68224.00
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5.40	4690.50	Rupees Four Thousand six hundred ninty & fifty Paise Only	25329.00
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	97.20	70.04	Rueeps seventy & four paise only	6808.00
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 27 I. 5.31.1)	Sqm	130.80	343.44	Rupees Three hundred forty three & forty four Paise only	44922.00
7	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	144.00	924.48	Rupees Nine hundred twenty four & Forty eight Paise Only	133125.00

Sl: Signature of the Contractor

Executive Engineer.

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010